BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/RD/WORK_INDENT48772

NAME OF WORK: Filling of potholes in Ward No. 15 T.Dasarahalli

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri Venkataramu (AM Enterprises)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications with all lead & lift charges & as per direction of Engineer-In-Charge of Work.	Cum	655.40	1672.0	Rupees One Thousand Six Hundred Seventy Two Only
2	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40mm KSRRB M3000-4, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specificatiosn with all lead & lift charges & as per direction of Engineer-In-Charge of Work.	Sqm	1215.20	274.0	Rupees Two Hundred Seventy Four Only

ವೆಂಕಟರಮಣ
Signature of the Contractor,

Executive Engineer
Dasarahalli Division

Scanned with CamScanner